



Design Notes:

- Reinforced to Meet H-10 Loading
- Additional Risers Sold Separately
- Concrete Minimum 5000 psi at 28 days
- Stainless Steel Band Eliminates Grouting
- Cast In Seals Designed to Accept 4" PVC Pipe
- PVC Inlet & Outlet Tees & Residential Filter Provided
- Septic Side = 670 Gal
- Pump Station Side = 330 Gal
- Pump Sized to site Specific Conditions
- Tank should not have any more than 3' of fill over the top slab

EB/IA